

QUOTATION

TECHNO-COMMERCIAL PROPOSAL

SOLAR I & C SERVICE

QUOTATION

PROPOSED BY

TO-GEN SOLAR AGRO

TO

CHELLA MANI

MAIN INSTALLATION SITE, MADURAI



PROJECT DETAILS

Solution Provider	**TO-GEN SOLAR AGRO** 3/584-H, Mathur Village, Velliyankundram Group Via, Alagarkoil, Madurai – 625301
Customer Name	**CHELLA MANI**
Quotation No / Date	**QR202603/27.10.2026**
Customer / Site Address	**MAIN INSTALLATION SITE, MADURAI**
Proposed Solar Service	**Solar Installation & Commissioning (I&C)**
System Capacity	**54 kW**
Service Scope	**Complete Module Mounting, Structure Assembly, Cabling, Inverter Termination & Pre-Commissioning Testing**
Execution Methodology	**Standard Engineering Practice & Grid Synchronization**

TECHNICAL DETAILS

Sl. No	Product	Make	Specification	Qty
1	**Solar PV Panel**	Waaree / Vikram / Adani / Reputed Quality	mono	**01**
2	**On-Grid Inverter**	GROWATT / POLYCAB / Reputed Quality	54KW	**1**
3	**Mounting Structure**	Reputed Quality	GI, Normal Height	**1**
4	**DCDB,ACDB, Chemical Earthling**	Reputed Quality	Earth rod with 8Kg Chemical bag	**3**
5	**DC Cable**	Polycab	1C X 4Sq.mm Red cable and black cable	**As required**
6	**AC Cable**	Polycab	4C X 4.0Sq.mm and Earthling cable	**As required**
7	**Lightning Arrester**	Reputed Quality	Conventional Type	**1**





COMMERCIALS

Sl. No	Description	Total Price (INR)
1	**Solar Installation & Commissioning (I&C) Services – 54 kW** Design, Engineering, Installation and Commissioning (I&C) of 54 kW Solar System – Complete mechanical mounting, electrical cabling & terminations, inverter installation, earthing and pre-commissioning testing to grid synchronization.	23,434.54/-
	TOTAL	23,434.54/-
	GST (9% + 9%)	4,218.22/-
	GRAND TOTAL	27,652.76/-
	State Subsidy + Central Subsidy	123/-

COMMERCIAL TERMS AND CONDITIONS

Prices	Price quoted Ex-works
GST	17% included
Installation	Installation will be commenced by TO-GEN SOLAR AGRO after receipt of materials at the site and receipt of site clearance
Packing & Forwarding	Included, Single point delivery
Entry Tax	Inclusive
Payment	I. 80% of Final Price Offer in Advance. II. 10% to be paid after Material Supply of Solar Panels, Inverters and other BoS items. III. 10% after Installation and Commissioning.
Delivery	Within 7 Days from the date of receipt of the Purchase Order
Net Meter	Inclusive
Warranty	PV Modules: 12-years of Product, 30-years of Power Output Inverter : 8 Years
Quote Validity	This offer is valid up to 7 Days from the date of submission
Comprehensive Maintenance	5 years, site visit Every quarter after commissioning of the system for maintenance purpose.



IMPORTANT NOTES & DISCLAIMER

NOTES:

1. Customer shall arrange for civil foundation work, required space for inverter, module mounting structure, cable trays, and electrical room.
2. Water and Electricity for installation, fabrication and testing shall be provided free of cost by the customer.
3. The customer is responsible for safe storage of materials once delivered at site until completion of installation.
4. TANGEDCO feasibility approval, net-meter application, and commissioning will be facilitated by TO-GEN SOLAR AGRO.
5. Any statutory charges, deposits, or application fees payable to TANGEDCO/CEIG shall be borne directly by the customer.
6. Solar generation depends on seasonal climatic conditions, direct sunshine hours, shading, and regular panel cleaning by the customer.
7. Internet connectivity (Wi-Fi / LAN with stable signal near the inverter) for remote monitoring logger must be provided by the customer.

DISCLAIMER:

Warranty is not covered for the damages due to natural calamities, acts of god, theft & vandalism, site related problems, attempt of servicing by a third party and negligence of customer. We are not liable for any type of compensation for damages caused to person, place and things due to the above-mentioned reasons. The warranty will become null and void if the installation is done by people other than those authorized by TO-GEN SOLAR AGRO.

BANK ACCOUNT DETAILS

Account Name:	TO-GEN SOLAR AGRO
Account No:	120029515077
Bank & Branch:	CANARA BANK, Alagarkoil, Madurai
IFSC Code:	CNRB0016228
UPI ID:	325547505515077@cnrb

QR CODE

SCAN TO PAY

EMPANELLED & REGISTERED VENDOR

TO-GEN SOLAR AGRO

3/584-H, Mathur Village, Velliyankundram Group Via, Alagarkoil, Madurai – 625301
GSTIN: 33BJWPA4500M1Z6 • Contact: +91 63803 29294
Quotation Ref: QR202603

For TO-GEN SOLAR AGRO,

P. Alagu Pandi

P. Alagu Pandi
Proprietor
Date: 27.10.2026